

BRUHAT BANGALORE MAHANAGARA PALIKE

APPROVED SCHEDULE - B

Name of the Work: Improvements and Asphaltting to Veeranna layout Gautam Book Store Road and Thindlu Surroundings in Ward No. 09, Vidyaranyapura Sub Division.


Sl. No.	Approved Qty.	Description	Unit	Rates KRIDL	
				In Figures	In Words
1	244.21	Earth work excavation by manual means in ordinary soil involving an average horizontal throw upto 2 meters and an average lift upto 0.5m, excavated surface leveled and sides neatly dressed, the disposed earth to be leveled neatly after breaking of clods etc complete as per specifications and directions of engineer in charge of the work	Cum	83.16	Rupees Eighty Three and Sixteen Paise Only
2	663.00	Removing B.S Slab of Drain and stacking etc complete as per specifications and directions of engineer in charge of the work	Sqm	63.72	Rupees Sixty Three and Seventy Two Paise Only
3	663.00	Refixing stone slabs of drains and pointing in C.M (1:3) etc complete as per specifications and directions of engineer in charge of the work	Sqm	78.84	Rupees Seventy Eight and Eighty Four Paise Only
4	1105.00	Scarifying kankar/gravel/metal crust upto 150mm thick with pick axes and disposal of stuff within a lead of 100 meters including cost of all labour charges etc complete as per specifications and directions of engineer in charge of the work	Sqm	25.92	Rupees Twenty Five and Ninety Two Paise Only
5	221.00	Providing, laying spreading and compacting graded stones aggregate to wet mix macadam specifications including premixing the material with water at OMC in mechanical mix plant carriage of mixed method of tipper to site, laying, in uniform layers with paver in sub base course on well prepared surface and compacting with vibratory roller to achieve the desired density etc complete as per specifications and directions of engineer in charge of the work	Cum	1713.96	Rupees One Thousand Seven Hundred Thirteen and Ninety Six Paise Only
6	1105.00	Providing and applying primer coat with S.S. bitumen emulsion on prepared surface of granular base such as WBM, WMM including cleaning of road surface and spraying primer at the rate of 0.60 Kg / sqm using mechanical means etc complete as per specifications and directions of engineer in charge of the work	Sqm	28.08	Rupees Twenty Eight and Eight Paise Only
7	44.20	Providing and laying bituminous concrete 40mm thick with hot mix plant, using crushed aggregates of specified grading, premixed with bituminous binder and filler, transporting the hot mix to work site, laying with paver finisher to the required grade, level and alignment, rolling with smooth wheeled, vibratory and tandem roller to achieve the desire compaction as per MORTH specification clause No. 500.9 complete In all respects as per specifications. MORTH specification NO. 509, using 10/60 TPH capacity H.M.P with Mechanical paver Gr-II (30 to 45 mm) with 6% VG-30 etc complete as per specifications and directions of engineer in charge of the work	Cum	7699.32	Rupees Seven Thousand Six Hundred Ninety Nine and Thirty Two Paise Only

EXECUTIVE ENGINEER-4
KRIDL, BBMP, DIVISION,
BANGALORE-560 010


H.V. Y
11/7/11

Sl. No.	Approved Qty.	Description	Unit	Rates	
				KRIDL	
				In Figures	In Words
8	219.78	Lead for Disposal of Debris shall be payable at carage rates by Mechanical means including loading and unloading. From 0.00 to 11.90 Km etc complete as per specifications and directions of engineer in charge of the work	Cum	106.34	Rupees One Hundred Six and Thirty Four Paise Only


EXECUTIVE ENGINEER-4
 KRIDL, BBMP, DIVISION,
 BANGALORE-560 010


 Executive Engineer
 Byarayanapura Division
 BBMP, Bangalore - 92

11/7/16


 11/6/17